

GCC Rail-Ready Checklist: 10 Operational Steps for B2B Shippers

A structured operational audit framework for supply chain leaders preparing to transition cross-border freight from road haulage to the UAE–Oman Hafeet Rail Corridor.

Strategic Purpose: Operating cross-border rail freight requires aligning digital customs data, physical loading infrastructure, contractual terms (Incoterms 2020), and rolling-stock specifications. Complete this 10-step assessment prior to issuing RFPs or executing long-term block-train agreements.

PHASE 1: TRADE COMPLIANCE & DIGITAL CUSTOMS PRE-CLEARANCE

STATUS	STEP	ACTION ITEM & OPERATIONAL FOCUS	IMPLEMENTATION DETAILS & VERIFICATION STANDARD
☐	Step 1	HS Code Harmonization & Tariff Audit	Audit all cross-border SKUs against current UAE Federal Customs and Oman Customs tariff schedules. <i>Standard:</i> Ensure 8-digit HS Code alignment across both jurisdictions to enable automated Non-Intrusive Inspection (NII) scanning without physical customs holds at border terminals.
☐	Step 2	Digital Single-Window Data Onboarding	Register cargo manifest protocols on single-window digital trade platforms (e.g., UAE Advanced Cargo Information System / Oman Bayan system). <i>Standard:</i> Establish API integrations to transmit commercial invoices, certificates of origin, and packing lists 24 hours prior to rail dispatch.
☐	Step 3	Regulated & Hazardous Cargo Certification	Verify approval frameworks for specialized commodities (chemicals, polymers, agricultural perishables, or minerals). <i>Standard:</i> Obtain advance cross-border clearances for regulated goods to ensure uninterrupted transit through dedicated clearance windows.

PHASE 2: COMMERCIAL CONTRACTS & INCOTERMS 2020 ALIGNMENT

STATUS	STEP	ACTION ITEM & OPERATIONAL FOCUS	IMPLEMENTATION DETAILS & VERIFICATION STANDARD
☐	Step 4	Incoterms Transition: Road to Multimodal Rail	Transition commercial sales contracts from legacy road terms (e.g., FCA Factory or DDP Road Border) to multimodal terms: CPT or CIP (Named Intermodal Terminal) . <i>Standard:</i> Clearly define transfer-of-risk points at the

STATUS	STEP	ACTION ITEM & OPERATIONAL FOCUS	IMPLEMENTATION DETAILS & VERIFICATION STANDARD
			Al Ain Rail Ramp or Sohar Intermodal Yard within all Proforma Invoices and Purchase Orders.
☐	Step 5	Demurrage & Storage Liability Protocols	Update contract clauses governing free-time allowances at ICDs (Inland Container Depots) and terminal yards. <i>Standard:</i> Assign explicit financial liability between buyer, seller, and 3PL for terminal dwell fees, container detention, or customs re-inspection holds.

PHASE 3: FIRST-MILE / LAST-MILE INFRASTRUCTURE & DRAYAGE

STATUS	STEP	ACTION ITEM & OPERATIONAL FOCUS	IMPLEMENTATION DETAILS & VERIFICATION STANDARD
☐	Step 6	Facility Loading Infrastructure Audit	Conduct a physical audit of manufacturing plant / warehouse dispatch bays in Dubai, Sharjah, or Abu Dhabi. <i>Standard:</i> Ensure facility compatibility for container stuffing, heavy-lift forklifts, or overhead cranes supporting 20-ft, 40-ft, and 45-ft ISO equipment.
☐	Step 7	Feeder Drayage Strategy Selection	Select between Carrier-Haulage (bundled 3PL door-to-door execution via anchor operators like Noatum) or Merchant-Haulage (self-managed factory-to-rail road legs). <i>Standard:</i> Establish SLA agreements for shuttle trucking along E66/E11 corridors to ensure arrival within strict rail terminal loading windows.

PHASE 4: ROLLING-STOCK SELECTION & TECHNICAL EQUIPMENT

STATUS	STEP	ACTION ITEM & OPERATIONAL FOCUS	IMPLEMENTATION DETAILS & VERIFICATION STANDARD
☐	Step 8	Container & Wagon Payload Optimization	Evaluate volumetric weight versus axle-load capacities. Hafeet Rail supports heavy freight up to 32.4 tonnes per axle. <i>Standard:</i> Maximize payload density per wagon to capitalize on line-haul ton-kilometer cost structures (target ~40% net logistics savings).
☐	Step 9	Cold Chain & Reefer Power Setup	For perishable foods, agriculture, or pharma: verify reefer wagon power availability (central power-pack wagon or clip-on gensets). <i>Standard:</i> Test real-time IoT telematics for continuous temperature tracking (-25°C to +8°C) during the 100-minute line-haul transit.
☐	Step 10	Capacity Allocation & Rate Structure Securing	Engage rail operators/forwarders to lock in volume-tier discounts via annual TEU commitments or block-train slot allocations. <i>Standard:</i> Execute multi-year take-or-pay capacity agreements to protect priority slot access before full commercial line activation.

OPERATIONAL SIGN-OFF & AUDIT EXECUTION

Audit Conducted By: Name: _____ Title: _____	Approval / Sign-Off: Supply Chain VP / Director: Signature: _____	Audit Summary: ☐ Rail-Ready Approved ☐ Action Required (Gaps Found) Date: _____
---	--	---